9	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. Specification No. KRBS 500-1 MORTH Chapter 5 **Page No. 175/ Item No. 21.2/ PWD SR 2013-14**	**Sqm**			**Avg**				
	BTS Layout		1	70.00	5.00		350.0		
	Sheshadri Layout 2nd & 3rd cross		2	130.00	7.00		1820.0		
	Basic Rate	2.40					**2170.0**	**2.59**	**5620.00**
	Area Weightage 8%	0.19							
	Total	**2.59**							
10	KSRRB M400-17: Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per Specifications MORTH Specification No. 406 **Page No. 170/ Item No. 20.18/ PWD SR 2013-14**	**Cum**							
	BTS Layout		1	70.00	5.00	0.25	87.50		
	Sheshadri Layout 2nd & 3rd cross		2	130.00	7.00	0.25	455.00		
							542.50	**1121.04**	**608164.00**
	Basic Rate	1038.00							
	Area Weightage 8%	83.04							
	Total	**1121.04**							
11	KSRRB M500-15: Providing, laying and rolling with vibratory roller of built-up spray grout layer over prepared base consisting of a two layer composite construction of compacted crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be used with application of bituminous binder after each layer, and with key aggregates placed on top of the second layer to serve as a base confirming to the line, grades and cross-section specified, the compacted layer thickness being 75mm Complete as per specifications. MORTH specification No. 506 **Page No.177/ Item No. 21.16/ PWD SR 2013-14**	**Sqm**							
	BTS Layout		1	70.00	5.00		350.00		
	Sheshadri Layout 2nd & 3rd cross		2	130.00	7.00		1820.00		
						Total	**2170.00**		
	Considered 10% of Pot holes & Road Cuttings						**217.00**	**268.92**	**58356.00**
	Basic Rate	249.00							
	Area Weightage 8%	19.92							
	Total	**268.92**							